



Mansfield Municipal Light Department (MMED)

FY 2026 Capital Authorization Budget

- I. Executive Summary
- II. Capital Work Plan Summary (FY26)
- III. Capital Work Project Description
- IV. Projected Five Year Capital Plan
- V. Vehicle Replacement List

I. Executive Summary

Each year MMED establishes a 'Capital Work Plan' to invest ratepayer funds to improve system infrastructure and solidify Mansfield Electric's position as an industry leader in providing safe, reliable, and affordable electric energy to all its customers.

MMED has consistently had four primary objectives:

- I. Maintain a safe working environment for its employees.
- II. Invest in a strong system reliability performance.
- III. Provide affordable and competitive electric rates to its ratepayers.
- IV. Provide financial benefits to the Town of Mansfield that is consistent with sound financial management of the utility.

Each year the Engineering and Operations staff of MMED spend considerable time identifying critical infrastructure improvements and overall MMED operational needs to improve system operations. After defining each project along with stating its intended goal, each investment is estimated by the following breakdown;

- Equipment & Associated Materials
- Labor Expenses (MMED)
- Expenses for outside resources (Contractor, Police Details, etc.)
- Vehicle hours
- Timeline to complete
- Total Cost estimate

Finally, each investment in the 'Capital Work Plan' is classified in one of four type of projects:

1. One Time Projects - are to be completed in the Fiscal Year
2. Recurring Projects - with a period of two or more years
3. Billable Projects (ex. State Funded projects)
4. General Plant Improvements

From the analysis above, the MMED staff has identified **(7)** carry over projects from FY24 and FY25 and new FY26 capital project investments equal to **\$ 4,050,777** for FY26.

A summary breakdown of each is identified in the following chart:

FY2026 Budget

Capital Work Plan Cost Summary July 2025 to June 2026

IDENTIFIED PROJECTS									
Project	GL	Cat*	Carry Over Projects from FY25	Contracts & Vendors	Labor	Materials & Equipment	Police Details	Total	Labor Hours
FY 24-1	365-183	2 & 5	Gilbert ROW UG Cable Project (Jewell St UG)		\$180,000	\$20,000	\$1,000	\$201,000	1,385
FY 25-4	367-300	3	Balcom ST (1W1 Circuit) OH Reliability Construction	\$150,000	\$30,000		\$40,000	\$220,000	231
FY 24-10	365-220	2	Field Recloser		\$30,000	\$0	\$5,000	\$35,000	231
FY 24-13	390-300	1	Gates & Garage Door			\$160,000		\$160,000	-
FY 25-21	392-300	1	Digger (FY25 Approval with FY26 DELIVERY/PAYMENT)			\$340,000		\$340,000	-
FY25-22	362-500	2	Capacitors & Controls			\$97,000	\$5,000	\$102,000	-
FY 25-23	362-500	2	Gilbert Sub Distribution Regulator Controls		\$4,000	\$81,000		\$85,000	31
Total Specifically Identified				\$150,000	\$244,000	\$698,000	\$51,000	\$1,143,000	1,877
FY2026 Projects									
FY 26-1	365-300	2	Capacitor & Controls Replacement		\$30,000	\$412,444	\$5,000	\$447,444	250
FY 26-2	367-145	2	Clark Shore Condominium Association UG Conversion	\$5,000	\$15,000	\$50,000		\$70,000	125
FY 26-3	367-300	1	Justin Drive & Jewell St UG Construction	\$150,000				\$150,000	-
FY 26-4	367-300	1	S&C PMH 9 & PMH 12 Fault Interrupter Padmount Swiches			\$400,000		\$400,000	-
FY 26-5	392-300	1	Trailer Mounted UG Puller DDHXA-75-7500 ib	\$232,000				\$232,000	-
FY 26-6	392-300	1	Truck 10 with Plow			\$90,000		\$90,000	-
FY 26-7	392-300	1	Truck 30 (Standby Truck)			\$90,000		\$90,000	-
FY 26-8	392-300	1	Truck 18 (55' Bucket Truck with FY27 DELIVERY/PAYMENT)			\$400,000		\$400,000	-
FY 26-9	395-300	1	Omicron XFMR Test Set			\$70,000		\$70,000	-
Total Specifically Identified				\$387,000	\$45,000	\$1,512,444	\$5,000	\$1,949,444	375
GENERAL									
FY 26-10	364-300	4	Pole Replacements		\$8,000	\$30,000	\$2,000	\$40,000	67
FY 26-11	365-231	2	Animal Guard Project		\$18,000	\$50,000		\$68,000	150
FY 26-12	365-300	4	Overhead conductors & fiber system.	\$26,000	\$10,000	\$95,000	\$9,000	\$140,000	83
FY 26-13	367-300	4	Underground cable and conduit.	\$10,000	\$10,000	\$100,000	\$2,500	\$122,500	83
FY 26-14	367-300	4	UG Devices (PM Switchgear & Pothead Replacement)		\$10,500	\$120,000	\$11,000	\$141,500	88
FY 26-15	368-300	4	Transformers (Overhead & Padmount)		\$10,000	\$250,000	\$13,500	\$273,500	83
FY 26-16	369-300	4	New/Upgrade of services		\$6,667	\$10,000		\$16,667	56
FY 26-17	370-300	4	Metering Equipment		\$1,000	\$12,500		\$13,500	8
FY 26-18	373-300	4	Street Lighting		\$1,000	\$6,667		\$7,667	8
FY 26-19	390-300	4	Structures and Improvements			\$10,000		\$10,000	-
FY 26-20	392-300	4	Vehicle Accessories			\$40,000		\$40,000	-
FY 26-21	394-300	4	Tools for vehicles			\$50,000		\$50,000	-
FY 26-22	395-300	4	New Laboratory Equipment			\$20,000		\$20,000	-
FY 26-23	399-300	4	Computer Hardware & Software			\$15,000		\$15,000	-
Total Specifically Identified				\$36,000	\$75,167	\$809,167	\$38,000	\$958,333	626
Total FY26				\$573,000	\$364,167	\$3,019,611	\$94,000	\$4,050,777	2,878
Reimbursable Projects									
FY 26-24	415-200	3	Mass DOT Reimbursable Projects (Rt 140 & Rt 106)	\$ 394,875	\$ 200,000	\$ 195,869	\$ 87,750	\$ 966,343	1,000
FY 26-25	415-200	3	Mass DOT School St		\$ 29,218			\$ 29,218	146
FY 26-26	415-200	3	General Reimbursable Projects		\$ 30,000			\$ 30,000	150
Total Specifically Identified				\$ 394,875	\$ 259,218	\$ 195,869	\$ 87,750	\$ 1,025,561	1,296

1. Single Year Projects - are to be completed in the Fiscal Year
2. Multiple Year Projects - with a period of two or more years
3. Billable Projects (ex. State Funded projects)
4. Recurring Projects General Plant Improvements
5. Cable Materials Added to previously approved FY25 budget

**Mansfield Municipal Electric Department
Projected Five Year Plan
FY26-FY31 Capital Budget**

Description	FY26 Proposed	FY27 Projected	FY28 Projected	FY29 Projected	FY30 Projected	FY31 Projected
Carry Over Projects	\$ 1,143,000					
FY26 Projects						
Justine Dr & Jewell St UG Construction	\$ 150,000	\$ 90,000				
Clark Shore Condominium Association UG Conversion	\$ 70,000	\$ 390,000	\$ 390,000			
Vehicles:						
Truck 10 with Plow (New)	\$ 90,000					
Truck 30 (Replace-Standby)	\$ 90,000					
Truck 18 55' Bucket Truck (New-Delivery in FY27)	\$ 400,000					
Future Vehicles		\$ 350,000	\$ 360,000	\$ 375,000	\$ 400,000	\$ 425,000
Capacitor & Controls Replacement	\$ 447,444	\$ 250,000	\$ 50,000	\$ 50,000	\$ 50,000	
Others (UG Cable Pulling Trailer ; Omicron XFMR Tester ; PM Interrupter Sv	\$ 702,000	\$ 400,000	\$ 200,000	\$ 400,000	\$ 200,000	\$ 200,000
General (see note 1): Ongoing Annual Capital Requirements	\$ 958,333	\$ 1,006,250	\$ 1,056,563	\$ 1,109,391	\$ 1,164,860	\$ 1,223,103
Future Projects (FY27-FY31)						
Eastman Street Underground Project			\$ 250,000	\$ 250,000	\$ 250,000	
Facilities Enhancements		\$ 70,000	\$ 50,000	\$ 50,000		
Erick Rd UG Conversion			\$ 200,000	\$ 200,000	\$ 200,000	\$ 200,000
Field Reclosers		\$ 155,000	\$ 155,000	\$ 155,000	\$ -	
New East Street Underground (Feeder 2W5)			\$ 400,000	\$ 400,000	\$ 400,000	\$ 400,000
Bird Sub New Feeder Expansion (Future Feeders 2W5, 2W6, and 2W7)		\$ 450,000	\$ 450,000	\$ 500,000	\$ 650,000	\$ 850,000
Gilbert Sub Storage Shed (prev. approved FY24-8)		\$ 75,000	\$ 75,000			
Total Projected FY26 Capital Budget	\$ 2,907,777	\$ 3,236,250	\$ 3,636,563	\$ 3,489,391	\$ 3,314,860	\$ 3,298,103
Total Expected Expenditure (FY26 Capital + Carry Over)	\$ 4,050,777					
Reimbursable Projects	\$ 1,025,561	\$ 150,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000

NOTES:

(1) Ongoing Capital Budget projections based on projected proposed budget with 5% adder through FY31.

III. Capital Work Project Descriptions

Carry Over Projects from FY25:

- FY24-1: Gilbert ROW UG cable project –project to install new underground cable for the 1W1, 1W4 and 1W7 from Sweet's Pond to Justin Drive. As part of this plan three (3) circuits will be rerouted using the newly constructed underground duct system to increase reliability of power to all customers fed from these circuits.
- FY25-4: Balcom St (1W1 Circuit) OH Reliability Construction: – Replace 54 poles on Balcom St & Otis St to install new 477 AL spacer primary wire and transfer existing facilities to increase the reliability for customers in this area.
- FY24-10: Field Recloser Replacement Project Carry Over – Six (6) reclosers were purchased to replace the existing old field reclosers and controllers in the field. Six (6) more to be ordered in FY26.
- FY24-13: Garage & Motorized Gates – Replace and install new motorized gates. Four gates at High Street and 1 gate at Gilbert Street Substation. The new system will be capable of operating open/close from phone.
- FY25-21: Digger Truck - Digger Derrick (Expect FY26 delivery and payment): –Digger to be replaced is a 2000 Sterling truck with 23,338 miles on it. This project (FY25-21) was approved in FY25 with expected delivery in FY26.
- FY25-22: Capacitors & Controls Replacement – The material bid for this project will be awarded in FY25 (\$243,704) but the delivery of materials will be in FY26.
- FY25-23: Gilbert Sub Distribution Regulator Control – Replace three (3) voltage regulators at Gilbert substation

FY26 Capital Projects:

- FY26-1: Capacitors & Controls Replacement (Expect FY26 delivery and payment): – As a result of a reliability study conducted in 2024, it is desired to purchase new capacitors and controls and lindsey sensors to upgrade the existing antiquated caps and controls and connect them all to the SCADA system for better monitoring and control in order to minimize system losses during seasonal and system peak. The material cost of this project in FY26 & FY27 estimated to be \$447.4K and \$250K including materials & labor, respectively.
- FY26-2 Clark Shore Condominium Association UG Conversion – This area is currently fed from overhead poles running along the shore line in people's backyard. There are seven condominiums on this property as well as a house on an island. The pole line is going through a heavily treed area making it unaccusable and unsafe during storms and emergency restorations. It is proposed to secure an easement on the property

and install underground duct system to convert services from overhead to underground for easier maintenance and access. The cost of this underground conversion is spread over three years starting FY26.

- FY26-3 Justin Drive & Jewell Str UG Construction – Install a new manhole at the intersection of Balcom St & Justin Drive to connect to the last manhole on Justin Drive. It is also desired to continue and construct three risers from this manhole to connect to three underground getaway feeders out of Gilbert St. Two risers on Jewell St and one riser on Balcom St.
- FY26-4 S&C PMH9 & PMH12 Fault Interrupter PM Switches- These above the ground underground PM switches are made with solid state vacuum interrupters instead of regular NX type expulsion fuses. The operation is much safer and they coordinate with upstream and downstream protective devices better than fuses.
- FY26-5 Trailer Mounted UG Puller DDHXA-75-7500 lb – This cable pulling trailer helps pulling underground cables easier through manholes and prevents any possible damage to the cable jacket during the pulling process.
- FY26-6: Truck 10 with Plow- This new truck will replace old pickup truck 10 (see MMED Vehicle Replacement List on the last page for details).
- FY26-7 Truck 30- This new truck to replace the standby truck (see MMED Vehicle Replacement List on the last page for details).
- FY26-8 Truck 18 with Plow- This new 55' Bucket truck will replace old truck 18 (see MMED Vehicle Replacement List on the last page for details).
- FY26-9 Omicron XFMR Test Set- Transformer testing equipment to ensure the health of transformers before energization.

General Category:

- FY26-10: Pole Replacements – Increase system reliability by replacing old & deteriorated poles. MMED maintains a list of poles that need to be replaced.
- FY26-11: Animal Guard Installation Project – Install new animal guard products at potential animal contact locations to reduce outages. Locations include riser poles, transformer banks and switch/reclosers.
- FY26-12: Overhead Conductors & Fiber System – **Overhead Conductors:** increase system reliability by addressing unforeseen problems as they arise. This is for unforeseen overhead pole work that must be performed based on customer complaint, system conditions or storm repair. **Fiber System:** extend fiber network to connect field devices (i.e. Reclosers, Capacitors, Regulators) to the SCADA system

- FY26-13: Underground Cable & Conduit – Increase system reliability by addressing unforeseen problems as they arise. This is for unforeseen underground cable work that must be performed based on customer complaint, system outage conditions or storm repair.
- FY26-14: UG Devices (Pad Mount Switch & Pothead Replacement) – ***Pad Mount Switchgear Replacement:*** replace (4) live front switches per year with dead front switches to improve customer service reliability and operational safety. ***Pothead Replacement:*** replace porcelain pothead terminations (transition between OH and UG cable).
- FY26-15: Transformers (Overhead & Padmount) – This project serves two goals to: (1) meet new customer service deadlines by maintaining an adequate stock of transformers and (2) upgrading overloaded and aged transformers. These transformers (overhead & padmount) are used to serve customers in new subdivisions as well as upgrading/replacing transformers in older residential subdivisions to improve the reliability. This project will increase system reliability by replacing deteriorated transformers.
- FY26-16: New/upgraded electric services required – This is for the installation of new services, upgrade of existing service due to load or demand increase, or replacement of electric services that fail to meet customer load demands in timely manner.
- FY26-17: Metering Equipment – This is for the purchase and installation of metering equipment such as current transformers and potential transformers and related equipment to properly meter both residential and commercial customers systemwide.
- FY26-18: Street Lighting – This is for inventory & stock and used for the replacement of failed or damaged street light components to properly maintain the street lights in town.
- FY26-19: Structures and Improvements – This project will be used for MMED's structural improvements as needed.
- FY26-20: Vehicles Accessories– This is for the purchase of truck accessories for line operations, metering, and maintenance divisions.
- FY26-21: Tools for Vehicles – This is for the purchase of new tools for line operations, metering, and maintenance divisions.
- FY26-22: New Laboratory Equipment – Purchase of new equipment as required (i.e. PMI Single Phase Meter Recorder, testing equipment, etc.).
- FY26-23: Computer hardware and software – Purchase of new computers and software.

Reimbursement Projects:

FY26-24: Mass DOT Reimbursable Project (Rt140 & Rt106): This is a Mass DOT project to upgrade the intersection of Rt 140 & Rt 106 and widen Rt 106. National Grid will upgrade poles on Rt 106 to share with MMED. The scope of this project is from Fisher St to School St on Rt 106. MMED will relocate all its 1W5 circuit assets on poles located opposite side of the street to newly set poles by National Grid. This work requires to install approximately 2700' of new 477 AL Hendrix primary and 1/O Al triplex secondary wires and do some underground construction to relocate (1) street light and traffic control cabinets at the intersection and (2) three riser poles on Chauncy Street.

FY26-25: Mass DOT School St Reimbursable Project: This project involves relocation of a pole on School Street to widen the road.

FY26-26: General Reimbursable Customer Projects: – This project is for the work needed to meet the new customer service deadlines. All costs reimbursed by the customer.

V. Vehicle Replacement List

MANSFIELD MUNICIPAL ELECTRIC DEPARTMENT VEHICLE EXPENSE LIST													Date 4/17/25		
VEH.	YEAR	Years old	MANF.	MODEL	VIN	PLATE #	G.V.W.	FUEL	COST \$	Repair / PM Expenses	Mileage / Hours	Assigned to	VEH.	Replace	To Be Replaced in
513	2007	15	Ford	F350 Utility	1FTWTF31YX7EA84582	M80-333	10,700	gas	\$34,001.00	\$14,469.46	94626	Line	513	2019	FY19
530	2012	10	Ford	F250 4X4 P/U	1FT7X2B68CEC27564	M84020	8,800	gas	\$28,970.00	\$17,264.68	103377	Line Crew	530	2024	FY24
544	2001	21	IH	M4900	1HTSDAAR01H355787	M65557	35,000	diesel	\$129,470.00	\$62,298.70	51932	Line Crew	544	SOLD	?
528	2022	0	IH	MV607 Bucket	3HAEUMMR4NL462237	M9156A	35,000	diesel	\$258,363.00	\$6,993.70	3948	Spare Bucket	528	2037	FY37
523	2000	22	Sterling	L7501 Digger	2FZHAJBB5YAG46810	M58-142	36,220	diesel	\$144,790.00	\$51,320.80	22338	Spare Digger	523	2015	FY15
509	2008	14	Ford	Taurus	1FAHP24W68G123951	M79955	N/A	gas	\$18,950.00	\$4,342.37	33011	Plant	509	2023	FY23
510	2012	10	Ford	F250 4X4 P/U	1FT7X2B65CEA43053	M88522	5,080	gas	\$33,849.00	\$18,542.24	55331	Sta Op	510	2026	FY26
518	2011	11	IH	4400 /Posi-Plus	1HTMKAAR8BH362390	M84269	35,000	diesel	\$220,229.00	\$68,103.02	42888	Line Bucket	518	2026	FY26
511	2015	7	Ford	F250 4X4 P/U	1FT7X2B67FEB98501	M93043	8,800	gas	\$38,672.00	\$9,301.77	63741	Stores	511	2027	FY27
514	2015	7	Chev	K2500 Utility	1GB0KUEG1FZ544037	M93596	5,080	gas	\$39,997.00	\$6,687.83	103472	Line	514	2027	FY27
515	2020	2	Ford	Ranger R1F P/U	1FTER1FH4LLA52118	M53-630	5,080	gas	\$29,605.00	\$2,545.96	26154	Meter	515	2027	FY27
527	2006	16	Sterling	Swaploader	2FZACHCS66AM34219	M41-322	35,000	diesel	\$170,788.00	\$147,888.39	20700	Line	527	2031	FY31
516	2016	6	Ford	F350 Utility	1FTRF3B64GED28186	M97480	11,000	gas	\$34,247.08	\$9,761.68	38857	Meter	516	2028	FY28
521	2020	2	Dodge	Ram crew cab	1C6RR7KG2LS155245	M7438A	6,800	gas	\$35,000.00	\$2,420.17	10873	Line Foreman	521	2027	FY28
526	2015	7	Frtlnr	MT55/Utilimaster	4UZAARDU4FCGB9088	M89268	25,500	diesel	\$136,938.00	\$12,306.44	3933	Line UG splice	526	2027	FY27
517	2019	3	Ford	F350 Utility	1FD8X3B65KEC63135	M1839A	11,000	gas	\$47,824.47	\$2,549.33	12191	Station Op.	517	2031	FY31
522	2016	6	Ford	Ford F750	1FDYX7DE4GDA02779	M95923	35,000	diesel	\$229,641.00	\$32,481.31	28712	Line Bucket	522	2031	FY31
529	2016	6	IH	Terex Digger	3HAMMMMR8GL109952	M94817	37,000	diesel	\$249,902.00	\$26,047.43	11789	Line Digger	529	2031	FY31
501	2020	2	Chevy	Bolt EV	1G1FY6S07L4139003	M6980A	N/A	Elect	\$31,350.00	\$2,145.00	1015	Office	501	2035	FY35
520	2020	2	IH	MV607 Bucket	3HAEUMMR7LL391662	M1852B	35,000	diesel	\$271,982.00	\$9,880.43	1435	Line Bucket	520	2035	FY35
525	2020	2	INTL	MV607 Bucket	3HAEUMMRXLL858086	M6452A	33,000	diesel	\$297,885.00	\$6,658.28	16465	Line Bucket	525	2035	FY35
512	2017	5	Ford	F550 Dump	1FDUF5HY5HED14499	M99946	19,000	gas	\$72,547.59	\$4,820.62	12378	Line	512	2037	FY37
524	2022	0	Deere	310SL HL	1T0310HLCNF412703	M9157A		diesel	\$130,000.00	\$3,565.92	35	Backhoe	524	2052	FY52
									\$2,448,452.55	\$499,539.53					

Vehicle Replacement Guide Lines:

- Heavy Duty work vehicles (Digger and Bucket trucks) to be replaced every 15 years
- Small pickups to be replaced every 7 years
- Large pickups to be replaced every 12 years
- Pool cars to be replaced every 15 years
- Dump trucks to be replaced every 20 years
- Backhoe to be replaced every 30 years

Vehicle replacement is based on the guidelines above as well as the operational evaluation of the vehicle and useful remaining life.